

© PUNCH Consulting Engineers

This drawing and any design hereon is the copyright of the Consultants and must not be reproduced without their written consent. All drawings remain the property of the Consultants. Figured dimension only to be taken from this drawing. Consultants to be informed immediately of any discrepancies before work proceeds.

Date Drawn: 2021-01-07	
Drawn By: Colin O'Sullivan	
Colour Drawing:	



TO NOTE 5.)

1. ALL DIMENSIONS IN MILLIMETRES (mm) UNLESS NOTED OTHERWISE. 2. HYDRANT CHAMBERS SHALL BE COVERED WITH APPROVED HEAVY DUTY METAL COVERS TO IS 261 AND BS 5834 COVER AND FRAME SHALL BE SUITABLE FOR ROAD AND TRAFFIC CONDITIONS AND IS SUBJECT TO THE APPROVAL OF IRISH WATER. 3. HYDRANTS SHALL BE DOUBLE FLANGED DRILLED TO PN 16. THEY SHALL COMPLY WITH BS 750: 2012. THE HYDRANT SHALL INCORPORATE A SCREW DOWN GATE VALVE, UNDERGROUND "GUIDE TO HEAD" TYPE WITH SCREW DOWN CONNECTION OUTLET AND FALSE SPINDLE CAP AND IRON CHAIN.

5. HYDRANT CHAMBER TO BE CONSTRUCTED OF PRECAST CONCRETE UNITS OR HIGH DENSITY BLOCKWORK. ALTERNATIVELY PROPRIETARY PREFABRICATED CHAMBER UNITS MAY ALSO BE USED, SUBJECT TO APPROVAL FROM IRISH WATER.

6. CONCRETE CHAMBERS SHALL BE SURROUNDED BY A MINIMUM OF 150mm

COMPACTED CLAUSE 804 MATERIAL AS PER STD-W-14.


7. DUCTILE IRON PIPES AND FITTINGS TO BE IN ACCORDANCE WITH IS EN 545. 8. 200mm ALL AROUND, 100mm DEEP CONCRETE PLINTH WITH PROTECTIVE

STAINLESS STEEL METAL BAND AROUND COVERS IN GREEN AREAS.

9. THRUST BLOCKS (NOT SHOWN ON DRAWING), TO BE PROVIDED AS PER STANDARD DRAWING STD-W-40 AT ALL TEES, BENDS, TAPERS, DEAD ENDS AND PIPES AT STEEP

FUSION WELD

10. ANTI CORROSION TAPE TO BE PROVIDED AROUND BURIED FLANGES. 11. ALL CONCRETE TO BE IN ACCORDANCE WITH IS EN 206.



FLOOR PLAN FIRE HYDRANT CHAMBER (PRECAST CONCRETE CONSTRUCTION)

Rev	Amendment	By	Date	Client:		J	Job Titl
C01	ISSUED FOR PLANNING	DT	07/10/2022	ctient.	1 4 1	D	Dwg Tit
						J	Job No:
					Comhairle Cathrach Chorcaí Cork City Council		

NOTES:

- 1. ALL DIMENSIONS IN MILLIMETRES (mm) UNLESS NOTED OTHERWISE.
- 2. HYDRANT CHAMBERS SHALL BE COVERED WITH APPROVED HEAVY DUTY METAL COVERS TO IS 261 AND BS 5834 COVER AND FRAME SHALL BE SUITABLE FOR ROAD AND TRAFFIC CONDITIONS AND IS SUBJECT TO THE APPROVAL OF IRISH WATER.
- 3. HYDRANTS SHALL BE DOUBLE FLANGED DRILLED TO PN 16. THEY SHALL COMPLY WITH BS 750: 2012. THE HYDRANT SHALL INCORPORATE A SCREW DOWN GATE VALVE, UNDERGROUND "GUIDE TO HEAD" TYPE WITH SCREW DOWN CONNECTION OUTLET AND FALSE SPINDLE CAP AND IRON CHAIN.
- 4. ALL HYDRANTS SHALL BE CLOCKWISE CLOSING.
- 5. HYDRANT CHAMBER TO BE CONSTRUCTED OF PRECAST CONCRETE UNITS OR HIGH DENSITY BLOCKWORK. ALTERNATIVELY PROPRIETARY PREFABRICATED CHAMBER UNITS MAY ALSO BE USED, SUBJECT TO APPROVAL FROM IRISH WATER.
- 6. CONCRETE CHAMBERS SHALL BE SURROUNDED BY A MINIMUM OF 150mm COMPACTED CLAUSE 804 MATERIAL AS PER STD-W-14.
- 7. DUCTILE IRON PIPES AND FITTINGS TO BE IN ACCORDANCE WITH IS EN 545.
- 8. 200mm ALL AROUND, 100mm DEEP CONCRETE PLINTH WITH PROTECTIVE STAINLESS STEEL METAL BAND AROUND COVERS IN GREEN AREAS.
- 9. THRUST BLOCKS (NOT SHOWN ON DRAWING), TO BE PROVIDED AS PER STANDARD DRAWING STD-W-40 AT ALL TEES, BENDS, TAPERS, DEAD ENDS AND PIPES AT STEEP SLOPES.
- 10. ANTI CORROSION TAPE TO BE PROVIDED AROUND BURIED FLANGES.
- 11. ALL CONCRETE TO BE IN ACCORDANCE WITH IS EN 206.
- 12. TEE BRANCH: DEPTH OF TAKE-OFF PIPEVORK < 900mm, TAKE-OFF TEE MAY BE ROTATED TO ENSURE MIN. DEPTH OF COVER IS MAINTAINED, OR ALTERNATIVELY, PROVIDE PROTECTION TO TAKE-OFF PIPE.

Title: CLOVERHILL SOCIAL HOUSING DEVELOPMENT Scale @ A1: 1:10 Title: PROPOSED CONSTRUCTION DETAILS SHEET 5 echnician Check: Shane Slattery IO: 194191 Model Ref: CLO-PUNCH-XX-XX-M2-0525 Drawing Status: A0 gineer Check: Mike O'Connor Approved: David O'Donovan Dublin Limerick Cork Galway Glasgow Document No: CLO-PUNCH-XX-XX-DR-C-0525 Elm Court, Boreenmanna Road, Cork, T12 HHW2 consulting engineers Revision No: CO1 IRL: +353 21 462 4000 www.punchconsulting.com