

## TREE SURVEY

**Proposed Cycle Route,  
Glanmire,  
Co Cork.**

**January 2022**

## **CONTENTS**

Summary

1. Introduction

2. Description of Existing Trees

3. Arboricultural Impact Assessment

4. Recommendations – AMS

Limitations & References

Appendix 1: Tree Survey Schedule

## SUMMARY

This report presents a record of those trees existing within or adjacent to a proposed cycle route proposed along the existing road (R639) which runs parallel to the Glashaboy River. The report considers those trees that may potentially be impacted by the development proposal. Trees have been surveyed as individuals or tree groups in accordance with BS 5837 (2012). The site tree survey was undertaken on 13<sup>th</sup> January 2022 by Cunnane Stratton Reynolds arborist;

Keith Mitchell    Diploma Arboriculture (Level 4)  
                         Technician Member Arboricultural Association (UK)  
                         Tree Risk Assessment Qualification (International Society of Arboriculture)  
                         MA(Hons) Landscape Architecture  
                         Member of the Irish Landscape Institute  
                         Chartered Member of the Landscape Institute (UK)  
                         Diploma EIA Management

This survey and report are based on the topographic site survey information supplied in the following drawing;

- OCSC – C1001-OCSC-XX-XX-DR-C-0002-0006-OPTION 2

A full survey record is presented in Appendix 1, together with accompanying drawings Tree Constraints Dwg No 22104\_T\_101, Arboricultural Impact Assessment Dwg No 22104\_T\_102 and Tree Protection Plan Dwg No 22104\_T\_103. After introducing the terms of reference and the methodology of the survey, the report summarises the survey findings in an overview of the existing tree cover along the proposed route.

A total of twenty-three individual trees and three tree groups were recorded as part of the survey.

For reasons of practicality large groups of similar trees may be assessed as tree groups. Where assessment takes the form of a tree group – any trees of particular arboricultural significance or relevance to proposed scheme within these groups may also be identified and assessed as an individual within the group. Every effort has been made to access all trees for inspection, however where site conditions prevent full physical access, some measurements may be visually estimated. Where trees are heavily obscured by existing ivy growth a best assessment is made however this must be considered preliminary until full visual access is available.

The route enjoys a number of street trees and riverbank trees of varying maturity and quality. The proposed layout will necessitate the removal of some existing street trees, with replacement tree planting implemented as part of the scheme to mitigate against proposed tree removals.

The report concludes with recommendations for protection measures to ensure the conservation of retention trees during the proposed development.

# **1. INTRODUCTION**

## **Terms of Reference**

Cunnane Stratton Reynolds (CSR) were instructed to undertake a tree survey, to inform the proposed development of a roadside cycle route.

Following a site survey, CSR considered those tree and tree groups that might potentially be impacted by the proposed scheme and produced a subsequent tree survey report presenting our findings, (in accordance with BS 5837:2012), together with recommendations for their best practice management in relation to the proposed development.

This involved a survey of the principal trees / tree groups concerned in accordance with BS 5837 (2012).

Documents supplied to CSR for purposes of conducting a tree survey include:

- OCSC – C1001-OCSC-XX-XX-DR-C-0002-0006-OPTION 2

## **Site Inspection & Methodology**

The site was surveyed on 13<sup>th</sup> January 2022 by a qualified Arborist. A visual inspection from the ground was performed on all relevant existing trees / tree groups on site. Where access allowed, principal individual trees were tagged and examined before critical measurements were taken and observations made.

A description was recorded of each tree / group of trees, their species, age class, all relevant measured dimensions (height, stem diameter, crown spread radii and crown clearance height) and an assessment of the tree health / vitality, structural form, life expectancy and quality categorisation. Any recommended remedial works required are outlined. Significant tree groups within/bounding the site are subject to group description and assessment, in accordance with BS 5837 (2012).

The findings of the survey are recorded and presented in this Tree Survey Report and Tree Schedule (Appendix 1). A Tree Classification and Constraints drawing was produced to inform the design process. An Arboricultural Impact Assessment and Tree Protection Proposals were considered in relation to the proposed scheme.

This report is subject to the scope and limitations as given at the end of the report.

## **Accompanying Drawings**

The tree survey report should be read in conjunction with;

- Tree Classification & Constraints (Dwg No 22104/T/101).
- Arboricultural Impact Assessment (Dwg No 22104/T/102).
- Tree Protection (Dwg No 22104/T/103).

A1 size colour coded drawings accompany this report, (monochrome drawings should not be relied upon). These drawings are based upon the topographical drawings supplied to CSR.

## **Site Location**

The proposed cycle route is located between the existing public roadway (R639) and the River Glashaboy, between Glanmire village to the north and the N8 roundabout to the south – a total distance of approximately 1.4km.

## 2. DESCRIPTION OF EXISTING TREES

2.1 The area of trees surveyed, (approximate survey area highlighted red – Fig 1), follows the Glashaboy River in a north to south alignment towards the River Lee.



Figure 1: Low resolution satellite image of approximate tree survey area in red (courtesy of Google Earth).

A total of twenty-three individual trees and three tree groups were recorded as part of the survey.

Their location, size and quality category may be reviewed with reference to the accompanying Tree Survey Dwg No 22104/T/101 and the tree survey (Appendix 1).



## 2.2 Photographic Summary of Trees Surveyed



T386



T387



T389



T390



T391




T392



T393




T394



T395



T396



T397



TG1



TG2



TG3



TG3



TG3



T398



T399 & T400





T401



T402




T403



T404



T405



T406



T407




T408



TG4

2.3 The proposed route follows an existing corridor, the boundaries of which are defined steep wooded hillsides to the west and the River Glashaboy to the east. A pedestrian footpath and adjoining grass verge currently existing between the roadways eastern edge and a continuous low wall running along the top of the riverbank. A pedestrian footpath runs from along the western road edge from Glanmire village for approximately a third of the route before transitioning into a grass verge.

It is proposed to develop a new cycle path and footpath on both side of the existing road as illustrated in typical section below. This will necessitate the removal of some existing street Sometrees along the eastern side of the road, however this will be mitigated through the planting of a new avenue of trees along the route.



Almost all the existing roadside trees are relatively young. Some additional trees are also found naturally occurring along the riverbank on the far side of the river wall, again these are generally young.

(Trees can sometimes become more valuable as collective groups, than they might be when considered solely as individuals in isolation - a grouping being generally of greater visual and ecological value. As such it should be noted that the cumulative value of evaluated Tree Groups often reflects an increased categorised value than might be awarded to the constituent trees if they were assessed in isolation as individuals).



### 3. ARBORICULTURAL IMPACT ASSESSMENT

3.1 This section discusses the potential impact of the proposed development on the existing tree cover on site and considers the need for mitigation measures, in accordance with BS 5837 (2012), for sustainable development.

3.2 Category 'U' trees are recommended for immediate removal, (fell or monolith to safe height), on general management grounds, irrespective of site development – none were identified as such during this survey.

#### Direct Loss of Trees

3.3 The proposed scheme is in direct conflict with a small number of trees and sections of hedgerow, which will require their removal to facilitate the proposed development.

Tag No	Tree Species	Tree Class	Number of trees
T388	Fagus sylvatica	B2	1
T389	Fagus sylvatica	B2	1
T390	Fagus sylvatica	B2	1
T391	Fagus sylvatica	B2	1
T392	Fagus sylvatica	B2	1
T393	Fagus sylvatica	B2	1
T394	Fagus sylvatica	B2	1
T395	Fagus sylvatica	B2	1
T396	Fagus sylvatica	B2	1
T397	Fagus sylvatica	B2	1

#### Indirect Impacts

3.4 Cognisance must also be given to indirect impacts - in particular care must be taken to ensure the proposed development and ancillary works do not represent an unacceptable conflict with the calculated 'Root Protection Area' of the existing trees proposed for retention.

Disturbance of 'Root Protection Area' may just as readily kill or destabilise a tree over time, by means of root damage/severance and or earth compaction/covering preventing essential transfer of water, air and nutrients to roots.

The remaining trees bar one are all on the far side of the river wall and a sufficient distance from the works that it is not anticipated they will be adversely impacted. One small Hawthorn tree (T387) will require protection during the works if it is to be retained.

Good planning and site management will be required during construction works to ensure these areas are not adversely impacted by construction activities. The use of tree protection fencing as set out in tree protection drawing Dwg 22104A\_T\_103 to exclude access to root protection areas will be critical to avoiding detrimental impacts and their successful retention.

It is advised that the site manager must carefully review the tree protection drawing Dwg 22104A T 103, prior to commencement of works on site. The proposed tree

protection measures should be in place from the outset prior to the commencement of works. Any queries should be raised with the project Arborist prior to commencement of works on site.

Provided proper tree protection measures are adhered to it is not anticipated that any further trees will require removal due to indirect impacts.

### **Additional Considerations**

3.5 Scrub and tree removal should take place outside the bird nesting season (March – August).

The proposed development offers an opportunity for new tree planting which will assist in mitigating against proposed losses. It is suggested that a suitable street tree species is selected, and suitable ground conditions are provided in the form of a continuous trench to sufficient depth, with adequate drainage, backfilled with loosely compacted fresh screened topsoil, and suitable root-barrier installed along the edges to prevent conflict with road and pathways.

### **Summary**

3.6 Table 1 illustrates trees to be removed and their classification.

Table 1.

<b>Tree Class</b>	<b>Trees proposed for removal</b>
A Class Trees	0
B Class Trees	10
C Class Trees	0
U Class Trees	0
<b>TOTAL</b>	<b>10</b>

### **Tree Protection**

3.7 Adequate protection and so successful retention of those trees to be retained within the land take area, will be achieved by rigidly excluding all construction activities from tree root protection areas by fit for purpose barriers/fencing and/or additional ground protection.

3.8 Tree Protection Areas (TPAs) are proposed, as indicated on accompanying Tree Protection Plan (Dwg No 22104A\_T\_103). Protective fence line locations and details for these fences are also illustrated on the plan.

### **Services**

3.9 Any services that are planned as part of this project must also avoid designated 'Root Protection Area' of tree / tree groups for retention.



#### **4. RECOMMENDATIONS – Arboricultural Method Statement**

Recommendations for the specific measures advised regarding management of the trees in relation to this development are detailed within Appendix 1. These recommendations should inform, and be referred to in, the method statements submitted for approval prior to commencement by the responsible building/engineering and landscape contractors whose works (subject to grant of permission) will affect retained trees and the Tree Protection Areas.

##### **1. *Tree Works.***

Subject to the required permissions removal / felling works as specified on Dwg No 22104\_T\_102, should be performed prior to project commencement, by reputable contractors in accordance with BS 3998:2010 and current best practice. (Removal of scrub vegetation and ivy clearance should preferably be performed outside of the bird nesting season (1<sup>st</sup> March – 31<sup>st</sup> Aug). Tree felling should be preceded by a competent assessment as to the presence of any protected wildlife species, where required specialist advice should be sought if necessary).

##### **2. *Protective Fencing.***

Protective fencing (barriers) should be erected in the positions and alignments as indicated on the Tree Protection Plan (Dwg No 22104A\_T\_103).

Fencing should be in accordance with BS 5837:2012 unless otherwise agreed with the planning authority. Commencement of development should not be permitted without adequate protective fencing being in place. This fencing, enclosing the minimum tree protection areas indicated, must be installed prior to any plant, vehicle or machinery access on site. Fencing should be signed 'Tree Protection Area – No Construction Access'. Fencing is not to be taken down or re-positioned without written approval of the project Arborist. No excavation, plant or vehicle movement, materials handling or soil storage is to be permitted within the fenced tree protection areas indicated on plan.

##### **3. Monitoring & Compliance**

A professionally qualified Arborist is recommended to be consulted as required by the principal contractor or developer. It is advised that tree protection fencing, any required special engineering and supervision works etc must be included / itemised in the main contractor tender document, including responsibility for the installation, costs and maintenance of tree protection measures throughout all construction phases.

Copies of the Tree Survey and all accompanying drawings, a copy of BS 5837:2012 and NJUG 4 (2007) '*Guidelines for the planning, installation and maintenance of utility apparatus in proximity to trees*' should all be kept available on site by the contractor during development. All works are to be in accordance with these documents.

## **Limitations and Scope of this Survey Report**

This report covers only those trees individually inspected, (shown on the 'Tree Survey Drawings' and described in the 'Schedule'), reflecting the condition of those trees at the time of inspection. Some tree locations not on the topographic survey have been estimated (these tree numbers are denoted by an Asterix \*).

Inspection is limited to visual examination of the subject trees from the ground without; test boring, use of tomographic equipment, dissection, probing, coring, ivy removal or excavation to establish structural integrity.

The trees were not climbed and dimensions are approximate, but considered a reasonable reflection of the trees measurements. A number of trees were visually obscured by heavy ivy and or scrub growth, which could potentially hide from view existing faults or weaknesses, as such they would benefit from re-inspection upon removal of such growth. This survey can only therefore be regarded as a preliminary assessment.

There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the subject trees may not arise in the future. The currency of this survey report and its recommendations is one year.

The accompanying drawings are illustrative and based on the land (topographical) survey information supplied; CSR Ltd accept no legal liability or responsibility for any errors in the information contained in the supplied drawings.

CSR Ltd accept no responsibility for the performance of trees subject to pruning or other site works (including construction activities) not performed in strict accordance with recommendations as specified in this report and/or in accordance with BS 3998:2010 and BS 5837:2012

All retained trees mentioned in this report should be subject to expert re-inspection within 12 months and prior to completion of development works and public occupancy of the site.

This report was produced as a part of a planning application for the scheme; the author accepts no responsibility or liability for actions taken by reason of this report by the client or their agents unless subsequent contractual arrangements are agreed. Public disclosure or submission of any part of this report without title, or permission from the author, renders this report invalid and legally inadmissible.

## **References/Bibliography**

BS 5837 (2012). *Trees in Relation to Design, Demolition and Construction - Recommendations*. British Standards Institution. TSO, London.

BS 3998 (2010) *Tree Work - Recommendations*. British Standards Institution. TSO, London.

NJUG 4 (2007) *Guidelines for the Planning, Installation and Maintenance of Utility Apparatus in Proximity to Trees (Issue 2)*. National Joint Utilities Group.

## TREE SURVEY KEY

Information in the attached schedule is given under the following headings:

### Tree No.

Individual trees have been numbered and tagged on site with corresponding survey tag or treated as a group where appropriate (e.g. Woodlands/hedgerows) and illustrated on accompanying tree survey drawing.

### Species

Latin botanical names of species are provided

### Height

Overall estimated height given in meters (measured using Truplus 200 Laser Rangefinder).

### Stem Diameter

The diameter of the main trunk taken at a height of 1.5m on a single stem tree, or, on each branch of multi-stemmed (MS) trees.

### Crown Spread

The largest radius of branch spread is provided in meters for North / East / South and West directions.

### Height of lowest branch

The distance between ground level and first significant branch or canopy (and direction of growth) given in meters (m).

Any measurement or dimension that has been estimated (for offsite or otherwise inaccessible trees where accurate data cannot be recovered) is identified by the suffix #.

### Life stage

The tree's age is defined as:

Y = Young, in first third of life (tree which has been planted in the last 10 years or is less than 1/3 the expected height of the species in question).

MA = Middle Age, in second third of life (tree, which is between a 1/3 and 2/3's the expected height of the species in question).

M = Mature, in final third of life (tree that has reached the expected height of the species in question, but still increasing in size).

OM = Over mature (tree at the end of its life cycle and the crown is starting to break up and decrease in size).

V = Veteran Tree (exceptionally old tree).

#### Physiological Condition

The tree's physiological condition is defined as:

**Good** - Good vitality: normal bud growth, leaf size, crown density and wound closure

**Fair** - Average to below average vitality: reduced bud growth, smaller leaf size, lower crown density and reduced wound closure

**Poor** - Low vitality: limited bud growth, small chlorotic leaves, sparse crown, poor wound closure

**Dead** - No longer living.

#### Structural Condition

The trees structural condition is defined as:

**Good** - No major structural defects observed (possibly some minor defects)

**Fair** - Minor defects present, (such as bark wounds, isolated decay pockets or structure affected due to overcrowding), that could be alleviated by tree surgery/management

**Poor** - Major structural defects present such as extensive deadwood, decay or defective to the point of being dangerous. (Significant defects are noted e.g. decay, collapsing etc).

#### Preliminary Management Recommendations & Timescale

Recommendations actions based on limitations of survey – (may include further investigation and or assessment of suspected defects by means and or methods not undertaken / within the remit of this survey).

#### Estimated Remaining contribution (Years)

Life of the tree is given as;

- 10 < less than 10 years remaining
- 10 + in excess of 10 years remaining
- 20 + in excess of 20 years remaining
- 40 + in excess of 40 years remaining

#### Tree Quality Assessment Category

**U** Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years.

- Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other category U trees (e.g. where, for whatever reason, the loss of companion shelter cannot be mitigated by pruning)

- Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline
- Trees infected with pathogens of significance to the health and/or safety of other trees nearby, or very low quality trees suppressing adjacent trees of better quality

(NOTE: Category U trees can have existing or potential conservation value which it might be desirable to preserve).

## **A High quality**

*Trees of high quality with an estimated remaining life expectancy of at least 40 years*

A1 Trees that are particularly good examples of their species, especially if rare or unusual; or those that are essential components of groups or formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)

A2 Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features

A3 Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood-pasture)

## **B Moderate quality**

*Those trees of moderate quality with an estimated remaining life expectancy of at least 20 years.*

B1 Trees that might be included in category A, but are downgraded because of impaired condition (e.g. presence of significant though remediable defects, including unsympathetic past management and storm damage), such that they are unlikely to be suitable for retention for beyond 40 years; or trees lacking the special quality necessary to merit the category A designation.

B2 Trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals; or trees occurring as collectives but situated so as to make little visual contribution to the wider locality.

B3 Trees with material conservation or other cultural value

## **C Low quality**

*Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150 mm.*

C1 Unremarkable trees of very limited merit or such impaired condition that they do not qualify in higher categories.

C2 Trees present in groups or woodlands, but without this conferring on them significantly greater collective landscape value; and/or trees offering low or only temporary/transient landscape benefits.


C3 Trees with no material conservation or other cultural value.



# APPENDIX 1

Tag	Species	Height (m)	Crown Spread (m) N/S/E/W	Girth (mm)@ 1.5m	RPA circle radius (m)	Ht of lowest branch (m) & direction of growth	Life Stage	Estimated remaining contribution (years)	Physiological Condition	Structural Condition	Preliminary management recommendations	Category of retention + sub-category	Notes
386	Acer pseudoplatanus	9	4/4/4/4	280x2	4.74	2m all	MA	40+	Good	Fair		B1	riverbank
387	Crataegus monogyna	5	2/3/2/2	110	1.32	1m all	Y	40+	Good	Fair		B1	verge
388	Fagus sylvatica	9	3/3/3/3	270	3.24	2m e/w	MA	40+	Good	Fair		B1	verge
389	Fagus sylvatica	7	3/3/3/3	240/170	3.53	1m n	MA	40+	Good	Fair		B1	verge
390	Fagus sylvatica	5	4/4/3/3	240	2.88	2m all	MA	40+	Good	Fair		B1	verge
391	Fagus sylvatica	7	3/3/3/2	180	2.16	2m all	MA	40+	Good	Fair		B1	verge
392	Fagus sylvatica	5	3/3/3/2	170	2.04	2m all	MA	40+	Good	Fair		B1	verge
393	Fagus sylvatica	6	2/2/2/2	160	1.92	2m all	MA	40+	Good	Fair		B1	verge
394	Fagus sylvatica	7	3/3/3/2	230	2.76	2m all	MA	40+	Good	Fair		B1	verge
395	Fagus sylvatica	7	3/3/3/2	160	1.92	2m all	MA	20+	Good	Fair		C1	strimmer damage decay
396	Fagus sylvatica	8	3/3/3/2	220	2.64	2m all	MA	40+	Good	Fair		B1	verge
397	Fagus sylvatica	8	3/3/3/2	220	2.64	2m all	MA	40+	Good	Fair		B1	verge
TG 1	Acer pseudoplatanus	13	5/5/5/4	150x7	4.75	1m all	MA	40+	Good	Fair		B2	riverbank 6ft below path
TG 2	Acer pseudoplatanus	8	4/1/3/1	280	3.36	0m all	MA	40+	Fair	Fair		B2	riverbank 6ft below path
	Aesculus hippocastanum	8	3/5/3/2	100x9	3.60	0m all	MA	40+	Good	Fair		B2	riverbank 6ft below path
TG 3	Acer pseudoplatanus	7	3/3/3/3	130x3	2.70	0m all	MA	40+	Good	Fair		B2	3 trees riverbank
398	Acer pseudoplatanus	10	5/5/5/5	150x6	4.40	0m all	MA	40+	Good	Fair		B1	riverbank
399	Fraxinus excelsior	9	2/2/2/2	250	3.00	4m all	MA	40+	Good	Fair		B1	riverbank
400	Fraxinus excelsior	8	1/3/3/3	250	3.00	3m all	MA	40+	Good	Fair		B1	riverbank
401	Salix alba	5	5/5/3/2	350+300	5.52	0m all	MA	40+	Good	Fair		B1	riverbank
402	Acer platanoides	10	5/5/5/4	450	5.40	1m e/w	MA	40+	Good	Fair		B1	riverbank
403	Acer platanoides	9	6/4/5/0	400+200	5.36	2m all	MA	40+	Good	Fair		B1	riverbank
404	Fraxinus excelsior	10	5/6/5/4	220x4	5.28	0m all	MA	40+	Good	Fair		B1	riverbank
405	Acer pseudoplatanus	8	4/4/4/4	200x3	4.15	0m all	MA	40+	Good	Fair		B1	riverbank
406	Acer platanoides	8	2/1/2/1	200	2.40	2m all	MA	20+	Fair	Fair		B2	riverbank
407	Fraxinus excelsior	11	5/7/3/3	250x2	4.24	0m all	MA	40+	Good	Fair		B1	riverbank
408	Acer campestre	7	3/3/3/3	270	3.24	3m all	MA	10<	Fair	Poor		C1	split trunk at base






LEGEND

- CLASS A INDIVIDUAL TREE (HIGH QUALITY - RETENTION HIGHLY DESIRABLE)
- CLASS B INDIVIDUAL TREE (MODERATE QUALITY - RETENTION DESIRABLE)
- CLASS C INDIVIDUAL TREE (LOW QUALITY - RETENTION OPTIONAL)
- CLASS U INDIVIDUAL TREE (RECOMMEND REMOVAL)
- TREE GROUPS or HEDGEROWS (COLOUR REPRESENTING GROUP CLASSIFICATION)
- SCRUB VEGETATION
- CALCULATED ROOT PROTECTION AREA (RPA)

NOTE:  
THIS DRAWING IS PRODUCED IN COLOUR,  
MONOCHROME VERSIONS SHALL NOT BE  
RELIED UPON.

REV	DATE	AMENDMENT
CUNNANE STRATTON REYNOLDS LAND PLANNING & DESIGN		
GALWAY OFFICE ARDAONG, BALLYTRASNA, TUAM, CO GALWAY TEL 01 661 0419 EMAIL galwayinfo@csrlandplan.ie www.csrlandplan.ie		
PROJECT: GLANMIRE PROPOSED CYCLE ROUTE TREE SURVEY		DATE: JAN 2022
DRAWING: CONSTRAINTS & CLASSIFICATION		SCALE: 1:500 @ A0
		DRAWN: INIT CHECKED: KM
		DRAWING NO: 21724-T-101





LEGEND

CLASS A INDIVIDUAL TREE  
(HIGH QUALITY -  
RETENTION HIGHLY DESIRABLE)

CLASS B INDIVIDUAL TREE  
(MODERATE QUALITY -  
RETENTION DESIRABLE)

CLASS C INDIVIDUAL TREE  
(LOW QUALITY -  
RETENTION OPTIONAL)

CLASS U INDIVIDUAL TREE  
(RECOMMEND REMOVAL)

TREE GROUPS or HEDGEROWS  
(COLOUR REPRESENTING  
GROUP CLASSIFICATION)

SCRUB VEGETATION

CALCULATED ROOT  
PROTECTION AREA (RPA)


TREES & TREE GROUPS  
PROPOSED FOR REMOVAL

NOTE:

THIS DRAWING IS PRODUCED IN COLOUR,  
MONOCHROME VERSIONS SHALL NOT BE  
RELIED UPON.


CUNNANE STRATTON REYNOLDS		
LAND PLANNING & DESIGN		
GALWAY OFFICE ARDAONG, BALLYTRASNA, TUAM, CO GALWAY TEL 01 661 0419 EMAIL galwayinfo@csrlandplan.ie www.csrlandplan.ie		
PROJECT: GLANMIRE PROPOSED CYCLE ROUTE TREE SURVEY	DATE:	JAN 2022
	SCALE:	1:500 @ A0
	DRAWN: CHECKED:	INIT KM
	DRAWING NO:	21724-T-102





LEGEND

- CLASS A INDIVIDUAL TREE (HIGH QUALITY - RETENTION HIGHLY DESIRABLE)
- CLASS B INDIVIDUAL TREE (MODERATE QUALITY - RETENTION DESIRABLE)
- CLASS C INDIVIDUAL TREE (LOW QUALITY - RETENTION OPTIONAL)
- CLASS U INDIVIDUAL TREE (RECOMMEND REMOVAL)
- TREE GROUPS or HEDGEROWS (COLOUR REPRESENTING GROUP CLASSIFICATION)
- SCRUB VEGETATION
- CALCULATED ROOT PROTECTION AREA (RPA)
- TREES & TREE GROUPS PROPOSED FOR REMOVAL
- POSITION OF TEMPORARY PROTECTIVE BARRIERS TO EXCLUDE ALL CONSTRUCTION ACTIVITIES, (MACHINES & MATERIAL) TO BE INSTALLED PRIOR TO COMMENCEMENT OF WORKS IN ACCORDANCE WITH BS 5837:2012 (SEE TYPICAL DETAIL BELOW)



REV			DATE	AMENDMENT
CUNNANE STRATTON REYNOLDS LAND PLANNING & DESIGN				
GALWAY OFFICE ARDAONG, BALLYTRASNA, TUAM, CO GALWAY TEL 01 661 0419 EMAIL galwayinfo@csrlandplan.ie www.csrlandplan.ie				
PROJECT: GLANMIRE PROPOSED CYCLE ROUTE TREE SURVEY		DATE: JAN 2022		
DRAWING: TREE PROTECTION		SCALE: 1:500 @ A0		
		DRAWN: INIT CHECKED: KM		
		DRAWING NO: 21724-T-103		